

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
8-15-74  
AUG 15 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Niernberger of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Ni ernberger guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Co., Inc.

Complete Address: 200 W. Douglas, Wichita, Ks.

Lease Name: Post-Conger Well No. 3

Location: SE/ SE NE Sec. 16 Twp. 10 Rge. (E)(W) 16

County: Rooks Total Depth 3630' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

Gun pits, circulate heavy mud, displace 50 sk cmt plug at 500' thru  
drill pipe. Heavy mud to 240' & displace 25 sk cmt plug thru drill  
pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt  
to base of cellar.

Very truly yours,

Leo F. Massey  
Conservation Division Agent