

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-10-63
SEP 10 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kimbark Exploration Company,
201 University Blvd., Denver, Colorado.
Complete Address: _____

Lease Name Borger Well No. 1

Location NW-NW Sec. 23 Twp. 9 Rge. (E) (W)26

County Sheridan Total Depth 4170

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 8:30PM Day 4 Month 9 Year 1963

The Above well was plugged as follows:

226'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx cement
thru DP.. Heavy mud to 215', set plug with 1/4 Sk hulls and displaced
20 Sx cement thru DP. Heavy mud to 35', set plug with 1/2 Sk hulls and 10
Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 9/10/63

INV. NO. 7723-4