

KANSAS

AL STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-12-68
JUL 12 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address: 1515 Wichita Plaza Building, Wichita, Kansas. 67202

Lease Name Corke Well No. 1

Location SE SENE
440' FEL & 2200' FNL Sec. 24 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4150

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 1: AM Day 10 Month 7 Year 1968

The Above well was plugged as follows:

225'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. -Pulled DP to 1450' -and- displaced 100 Sx. cement thru
DP from 1450' to 1125'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 7/12/68
INV. NO. 8093-W