

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
1-15-73  
JAN 15 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Donald C. Slawson,  
Complete Address 408 One-Twenty Building, Wichita, Kansas.  
Lease Name McFadden Well No. A-1  
Location SE-NE-NE Sec. 9 Twp. 9 Rge. (E) (W) 27  
County Sheridan Total Depth 4030'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Slawson Drilling Company, Incorporated,  
Address Above License No.         
Operation Completed: Hour 9:30 AM Day 11 Month 1 Year 1973

The above well was plugged as follows:

285'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 110 Cu. Ft. cement  
Thru DP from 1350' to 1025'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 1/15/73

INV. NO. 6856-W