

KANSAS

*AP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
10-21-68  
OCT 21 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Kaiser-Francis,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name Rogers Well No. E-4

Location SE-NW-NE Sec. 11 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4060'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 5:30PM Day 15 Month 10 Year 1968

The Above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1170'.

Circulated hole with heavy mud. Pulled DP to 1395' and displaced 100 Sx. cement thru  
DP from 1395' to 1070'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from  
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Dickel*  
Well Plugging Supervisor

INVOICED

DATE 10/21/68  
INV. NO. 86594