

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 5 5-71 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Lindexman Well No. 2

Location SE-NW-SW Sec. 12 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4155'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 11:30 AM Day 31 Month 3 Year 1971

The above well was plugged as follows:

231'--8 5/8" Surface casing, cement circulated with 160 Sx.

4155'--4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 4080'. Top perforations @ 3300'.

Pushed plug to 3250', sanded back to 3200' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing (1505') and squeezed well initially with 5 sacks gulls and 5 sacks gel then 100 Sx. cement from 1450' to 1125' then 22 sacks gel from 1125' to 250' and followed with 25 Sx. cement from 250' to 175' then 3 sacks gel from 175' to 50' and finally 20 Sx. cement from 50' to bottom of cellar. Maximum pump-in pressure-500#.

Final shut-in pressure-300#. (Mudding and cementing by Sun Oil Well Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dreibel
Well Plugging Supervisor

INVOICED

DATE 4/6/71
INV. NO. 3501-W