

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-19-73
MAR 19 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Lindenman Well No. 3

Location NW-SW-SW Sec. 12 Twp. 9 Rge. (E) (W)28

County Sheridan Total Depth 4153'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 4:00 PM Day 15 Month 3 Year 1973

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 175 Sx.
4152'--4 1/2" Production casing cemented on bottom. No plug back indicated. Top of perforations @ 3893'.

Pushed plug to 3850', sanded back from 3850' to 3825' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing (1530') and attempted to squeeze well with 5 sacks hulls, 9 sacks gel and approximately 2 bbls cement, gained circulation around surface casing. Ran available hose down surface casing and circulated out cement. On 3/15/73 Company Rig ran 2" tubing to 1525' and circulated gel with 30 sacks. Pulled tubing to 1475' and displaced 110 Cu. Ft. cement thru tubing from 1475' to 1150'. Pulled tubing to 275' and displaced 30 Cu. Ft. cement thru Tubing from 275' to 200'. Pulled tubing to 30' and circulated cement to bottom of cellar with 10 Cu. Ft. cement.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 3/19/73
INV. NO. 9143-u