

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-13-71
APR 13 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Lewis M. Mull,

Complete Address 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name Lyle W. Holley Well No. 1

Location SW-NE Sec. 2 Twp. 9 Rge. (E) (W) 31

County Thomas Total Depth 4230'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated.

Address 1125 Vickers KSB&T Building, Wichita, Kansas. License No.

Operation Completed: Hour 8:00 PM Day 9 Month 4 Year 1971

The above well was plugged as follows:

286'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 100 Sx. cement thru
DP from 1625' to 1300'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dickole*
Well Plugging Supervisor

INVOICED
DATE 4/13/71
INV. NO. 3548-W