

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
4-15-74
APR 15 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address 200 West Douglas, Wichita, Kansas 67202

Lease Name Conger Well No. 1

Location 100° N W/2 W/2 W/2 Sec. 15 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3631'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11 A Day 30 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3631' 8 5/8 csg set at 246' cwc

5 1/2 csg set at 3620' cw 125 sk cement.

Filled 5 1/2 csg W/sd to 3340' -dumped 4 sk cem. W/dump bailer. (3340-3310)

Cutoff and recovered 905' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water -100 lbs hulls -70 sk cement -8 sk gel & water -released 8 5/8 plug and pumped 50 sk cement by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Massey
Well Plugging Supervisor

DATE 4/2/74

INV. NO. 8854-W