

4-041371

5-19

158
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,585-0000

SW SW NW /4 SEC. 03, 09 S, 27 W
2970 feet from S section line
4950 feet from E section line

Operator license# 6066 Lease Mosier well # A-1

Operator: Skyline Petroleum County Sheridan 129.74

Address: P.O. Box 70 Well total depth 3992 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 239 feet
w/200 sx.cmt.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:30P.M. Day: 19 Month: May Year: 92

Plugging proposal received from: John Schippers

Company: Skyline Petroleum Phone:

Were: 5 1/2" casing set @ 3954' w/150 sx. cement.

Perf. @ 3723' - 3874'. Anhy. Perf. @ 2220'. Dakota @ 1480'.

W.L.M. 3800'.

Ordered 400 sks. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:45P.M., Day: 19, Month: May, Year: 92

Actual plugging report: Hooked-up to 5 1/2" casing. Squeezed 325 sx. cement w/400# hulls. Max. P.S.I. 250#. Shut in P.S.I. 150#.

Hook-up to 8 5/8" S.P. Squeezed 75 sx. cement with 100# hulls mixed in cement. Max. P.S.I. 250#. Shut in P.S.I. 100#.

Remarks:

Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO

Bottom plug(in place):YES X, CALC , NO Dakota plug:YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

I did X did not observe the plugging.

Dennis L. Hamel

(agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1992
CONSERVATION DIVISION
Wichita, Kansas

DATE 6-3-92

INV. NO. 35376