

15-179-20204-0001

API NUMBER 15- -

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW-NE-NW, SEC. 24, T 9 S, R 28 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5462

LEASE NAME Ochs OAKES WELL # 2 (SWD)

OPERATOR: L.G. STEPHENSON & CO. INC.
NAME & ADDRESS 670 EAST SIDE FIN. BTR.
7401 E. HELLOGG
WICHITA, KANS.
67202

COUNTY SHERIDAN # 134.88

WELL TOTAL DEPTH 4150 FEET

CONDUCTOR PIPE: SIZE 0 FEET

SURFACE CASING: SIZE 8 5/8 FEET 235

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL X SWD WELL X D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR NICHOLAS CASING PULLING LICENSE NUMBER 6698

ADDRESS Box 273 GENESO, KANS. 67444

COMPANY TO PLUG AT: HOUR: 10:00 A.M. DAY: 23 RD MONTH: AUG. YEAR: 1983

PLUGGING PROPOSAL RECIEVED FROM GEORGE NICHOLAS

(COMPANY NAME) NICHOLAS CASING PULLING (PHONE) 316-824-6483

WERE: 8 5/8" - 235 FT SP OUC #180 ST CMT, 4 1/2" CSG. SET @ 4140 FT.

OPEN HOLE 10 FT, BOTTOM PLUGGED OFF, COULD GET DOWN TO ONLY 2800 FT, AT BOTTOM 4 ST CMT, 15 FT SAND AND 4 ST CMT.

ORDERED 450 ST 50/50 Formix 6% GEL-3% CA-CL, 5 ST HULL'S & 8 5/8" PLUG.

PUMPED IN 8 5/8" S.P. WITH PUMP TRUCK.

PLUGGING PROPOSAL RECEIVED BY Marvin J. Smith (TECHNICIAN) 001C

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 23 RD MONTH: AUG. YEAR: 1983

ACTUAL PLUGGING REPORT

ORDERED 450 ST 50/50 Formix 6% GEL-3% CA-CL, 5 ST HULL'S, & 8 5/8" PLUG.

PUMPED IN 200 ST CMT, THEN 150 ST CMT #1/4 ST HULL'S MIXED IN,

RELEASED PLUG AND 100 ST CMT #1 ST HULL'S MIXED IN.

MAX. P.S.I 150 LBS., CEMENTED BY HALBURTON CMT.

REMARKS: _____

RECEIVED
STATE CORPORATION COMMISSION
8-29-83
AUG 29 1983

CONSERVATION DIVISION
Wichita, Kansas

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

INVOICED

DATE

8-31-83

REL. NO.

5391-W

SIGNED

Marvin J. Smith
(TECHNICIAN) 001C

FORM CP-2/3
33 REV. 6-83