

6 070900

3-3

159

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,986-0060

SE SE NW, SEC. 23, T 9 S, R 26 W/EX  
2970 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Borger Well # 1

Operator: Frontier Oil Co.  
Name & Address: 125 N. Market #170  
Wichita, Ks. 67202  
George A. Angle

County Sheridan  
Well Total Depth 4450 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 250

144.62

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A xx

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling License Number 5302

Address 125 N. Market #1720 Wichita, Ks.

Company to plug at: Hour: AM Day: 3 Month: Mar Year: 19 91

Plugging proposal received from D. L. Fennesy

(company name) Red Tiger Drilling (phone) \_\_\_\_\_

were: 8 5/8 250 ft. s.p. cwc w/165 sks 60/40 poz 2% gel 3% ca cl. Allied.

Elv. 2644. Anhy 2279. K.C. well. Mud 45 vis 9.0 weight 10 water loss.

Proposal 200 sks 60/40 poz 6% gel spot with drill stem; circ. heavy mud  
between all plugs. 1. 25 sks at 2280. 2. 100 sks at 1365 ; 3. 50 sks at  
300 ; 4. 10 sks at 40. 15 sks in rathole.

Plugging Proposal Received by *MS* Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None xx

Operations Completed: Hour: 8:30AM Day: 3rd Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Frontier ordered 200 sks 60/40 poz

6% gel 3% cc spotted and displaced cement circulated; heavy mud between plugs

1st plug at 2280 w/25 sks cement

2nd plug at 1365 w/100 sks cement w/1 sk f.c.

3rd plug at 300 w/50 sks cement

4th plug at 40 w/10 sks cement

RECEIVED  
STATE CORPORATION COMMISSION  
3-22-91  
MAR 22 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: 15 sks in rathole (cir) Cement by Allied Cementt  
(If additional description is necessary, use BACK of this form.)

INVOICED (If xxxxx did not) observe this plugging.

DATE APR 02 1991

Signed *Marion J. Schmidt*  
(TECHNICIAN) Marion J. Schmidt

INV. NO. 31269 MAY 03 1991

3-3