

6030597

API NUMBER 15-179-20,568-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NWNE1/4 SEC. 6, T. 9 S, R. 28 W1/4

4950 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6889

Lease Name MOSIER Well # 6-32

Operator: OXFORD EXPLORATION CO.

County SHERIDAN 134.23

Name & Address 1801 CALIFORNIA ST. STE 200

Well Total Depth 4130 feet

DENVER COLORADO

Conductor Pipe: Size _____ feet

80202

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor POE WELL SERVICE License Number _____

Address OBERLIN KANSAS

Company to plug at: Hour: PM Day: 11 Month: 5 Year: 19 85

Plugging proposal received from RED MARTIN

(company name) OXFORD EXP. CO. (phone) _____

were: 8 5/8 SET @ 208 w/200 SX. 4 1/2 SET @ 4005 w/200 SX. PERE 3874-77

PBTD 3950' ORDER SAND & COM. CNT. SHOOT OFF & RECOVER PIPE.

ORDER 180 SX. 60/40 PZ 6 GEL 3 BCL 8 5/8 W.P. HALLIBURTON CNT. CO.

NEUMAN WATER TRUCKS

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 PM Day: 5 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3800' SPOT w/BAILER 4 SX. COM. CNT.

RECOVERED 1279' OF 4 1/2. - Pump DOWN 8 5/8 3 SX. HULLS 20 SX. GEL.

100 SX. CNT. MIX. + 1 SX. HULLS 20 SX. GEL 8 5/8 W.P. 80 SX. CNT. MIX.

MAX. 450* PSI CLOSE IN 200 PSI PLUG. COMPLETE.

Remarks: _____
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 26 1985

INV. NO. 11233

11-5

RECEIVED
STATE CORPORATION COMMISSION
11-20-85
NOV 20 1985

Signed Carl Goodrow
(TECHNICIAN)

4
11-16-85
MMP