

6030031

00124-0000
179-20-446
KCC

P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- SW
C&SE, Sec. 18, T 9 S, R 26 WE
KCC

TECHNICIAN'S PLUGGING REPORT

_____ feet from N/S section line
_____ feet from W/E section line

Operator License # 6420

Lease Name TRANSUE Well # 1

Operator: KRM PETROLEUM
Name &
Address 1900 GRANT SUITE 300
DENVER, COLORADO 80203

County SHERIDAN

Well Total Depth 4030 feet #130.98

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor PERIFER WELL SERV. HALLIBURTON License Number 6967

Address OBERLIN KANSAS

Company to plug at: Hour: AM Day: 19 Month: 10 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO ROY BREGHY

(company name) K.R.M. (phone) _____

were: TAG BOTTOM WITH TUBING SPOT 60SX CEM. MIX. LAYDOWN
9 JOINTS - SPOT 2 1/2 SX GEL. LAYDOWN 40 JOINTS - SPOT 1 1/2 SX GEL.
LAYDOWN 43 JOINTS - TO 1200' CIRC. CEM. MIX. TO SURFACE.
Pump 100SX. CEM MIX DOWN BACK SIDE.

50/50 pot 6% GEL 3% CC

Signed Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30PM Day: 19 Month: 10 Year: 19 83

ACTUAL PLUGGING REPORT LOST FLUID (CIRC.) WHEN PIPE WAS PULLED
OUT OF HOLE WENT BACK IN WITH 100SX MORE MIX. WELL
WAS PLUGGED WITH 60SX CEM. 22SX GEL. 2.40SX CEM.
WITH 100 SX DOWN ANNULUS HOLE WAS FULL AND MAINTAINED
CEM. TO SURFACE.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
10-31-83
OCT 31 1983
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

Signed Carl Goodrow
(TECHNICIAN)

DATE 11-2-83

INV. NO. 6015-W

FORM CP-2/3
M Rev. 9-82