

6 031418

API NUMBER 15-

179-20,742-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SW, SEC. 12, T 9 S, R 28 W/EX

KCL
RT

2175-1320 feet from S section line

4950-3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Lindenman Well # 1

Operator: Pintail Petroleum

County Sheridan 133.57

Name & Address 412 E Douglas Suite 1
Wichita, Ks. 67202

Well Total Depth 4110 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casign Pullers License Number _____

Address Great Bend, Ks.

Company to plug at: Hour: _____ AM Day: 13 Month: Sept Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing (phone) _____

were: 8 5/8 set at 309 w/200 sks. 4 1/2 set at 4109 w/70 sks. PRTD 4067.
Perf 4013-38. Order sand and common cement. Pull pipe, order 250 sks

65/35 poz 10% gel. B. J. Titan Cement Co. Hensley water truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00AM Day: 13 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sand back to _____ w/4 sks common cement on sand

w/bailer. Recovered 1280 of 4 1/2 casing. Shot at 2340 anhy 1640. Sq 8 5/8 w/250 sks
cement blend w/500 lbs. hulls mixed in to max psi 500 lbs. Close in psi 300 lbs. Plug
complete.

RECEIVED
STATE CORPORATION COMMISSION
10-3-90
OCT 3 1990

Remarks: Anhy 2318 - 2337 CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 10-8-90

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 29555

Handwritten initials