

4-041637

12-1

D-22,095

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,659-0001

SW NW NE /4 SEC. 12, 09 S, 28 W
4290 feet from S section line
2310 feet from E section line

Operator license# 5011 Lease Yowell well # 1SWD

Operator: Viking Resources, Inc. County Sheridan 133,28

Address: 105 S. Broadway
Suite 1040
Wichita, Kansas 67202
Well total depth ^{old depth KCC RT} 4101 feet PB 2339'
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 287 feet
w/250 sxs.

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:00P.M. Day: 1 Month: December Year: 94

Plugging proposal received from: Terry Richardson

Company: Viking Resources, Inc. Phone:

Were: 4 1/2" casing set @ 2339' w/550 sxs. cmt. Perf. @ 2030' - 2100'.
Anhy. @ 2334' - 4 1/2" casing - cwc.
Ordered 150 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 3:15P.M., Day: 1, Month: December, Year: 94

Actual plugging report: 8 5/8" S.P. Pressured-up - cement at surface.
4 1/2" casing - squeeze down 4 1/2" casing with 150 sxs. cement with
200# hulls in cement. Max. P.S.I. 500#.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 19 1994
12-19-94
CONSERVATION DIVISION
WICHITA, KS

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 1-5-95

INV. NO. 41986 FEB 16 1995 MAR 16 1995

12-1