

4-041634

12-2

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,686-0000

W2 SE NE /4 SEC. 12, 09 S, 28 W
1980 feet from N section line
990 feet from E section line

Operator license# 5011

Lease Yowell well # 2

Operator: Viking Resources, Inc.

County Sheridan

Address: 105 S. Broadway
Suite 1040
Wichita, Kansas 67202

Well total depth 4090 feet ^{132.93}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 310 feet
w/180 sxs.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 2 Month: December Year: 94

Plugging proposal received from: Terry Richardson

Company: Viking Resources, Inc. Phone: _____

Were: 5 1/2" casing set @ 4088' w/150 sxs. cmt. Perf. @ 4024' - 4028'.
Anhy. @ 2350' - Dakota @ 1410' - W.L.M. 4020' - T.O.F. @ 2500'.
Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls
with 14 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:30P.M., Day: 2, Month: December, Year: 94

Actual plugging report: Rig up cementers to squeeze 5 1/2" casing with
25 sxs. cement with 100# hulls, followed with 14 sxs. gel, followed with
150 sxs. cement with 200# hulls. Max. P.S.I. 1000#.
8 5/8" S.P. - Squeezed 50 sxs. cement with 100# hulls. Max. P.S.I. 450#.
S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL _____

I did did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

RECEIVED
KANSAS CORPORATION COMMISSION
12-19-94
DEC. 19 1994
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 1-5-95

INV. NO. 41984

FEB 16 1995 MAR 16 1995

12-2