

4-041635

12-1

E-25,984

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,704-0001

SW NE NE /4 SEC. 12, 09 S, 28 W
4180 feet from S section line
1100 feet from E section line

Operator license# 5011 Lease Yowell well # 3

Operator: Viking Resources, Inc. County Sheridan

Address: 105 S. Broadway Well total depth 4065 feet
Suite 1040 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 285 feet
w/185 sxs.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:00P.M. Day: 1 Month: December Year: 94

Plugging proposal received from: Terry Richardson

Company: Viking Resources, Inc. Phone: _____

Were: 4 1/2" casing set @ 4063' w/1200 sxs. cmt. Perf. @ 3995' - 4000'.
Anhy. @ 2300' - Dakota @ 1400' - W.L.M. 2500' - T.O.F. @ 2500'.
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls
with 9 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:00P.M., Day: 1, Month: December, Year: 94

Actual plugging report: Rig up cementers to squeeze 4 1/2" casing with
25 sxs. cement with 100# hulls, followed with 9 sxs. gel, followed with
75 sxs. cement with 300# hulls. Max. P.S.I. 1000#. S.I.P. 1000#.
8 5/8" S.P. - Pressured-up to 700#. Cement at surface.

RECEIVED
KANSAS CORPORATION COMMISSION
12-19-94
DEC 19 1994
CONSERVATION DIVISION
WICHITA, KS

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 1-5-95

INV. NO. 41987

FEB 16 1995 MAR 16 1995

12-1