

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW-NW-SW, Sec. 12, T 9 S, R 28 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20, 109-#
2210 feet from N(S) section line
230 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5005
Operator: SUNBURST EXPLORATION Co
Name & Address ONE MAIN PLACE STE. 108
WICHITA, KANS. 67202

Lease Name LINDENMAN Well #1-(OULLO)
County SHERIDAN
Well Total Depth 1223 feet 39.75
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 262 RT KCL

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated RE-ENTRY - (OULLO)

Plugging Contractor BRADEN DEEM, INC. License Number 5331

Address 125 NORTH MARKET. STE. 1250 WICHITA, KANS. 67202

Company to plug at: Hour: 2:00 PM Day: 22 NO Month: MARCH Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO ELI HAMMERSONMIOT

(company name) BRADEN DEEM, INC. (phone) 216-262

were: 8 5/8" 262 RT KCL SP. CUC. NA - 4 1/2" CSG. FISH ET. 1156 FT -

WENT OUT OF HOLE AT 1223 FT ABANDONED AND PLUGGED.

SPOT WITH DRILL STEM, TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS
ORDER-200 SK 50/50 POZMIX GEL - CA-CL - 1 SK CELLO FLAME AND 8 5/8" PLUG - NO CIRCULATION

PROBLEMS ELY. 2698, Signed Eli Hammersonmiot (TECHNICIAN) 201C

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 PM Day: 22 NO Month: MARCH Year: 1984

ACTUAL PLUGGING REPORT

ORDERED 200 SK 50/50 POZMIX GEL - CA-CL - 1 SK CELLO-FLAME AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM, TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 1220 FT W/100 SK CMT W/1 SK CELLO FLAME - 2ND Plug @ 600 FT W/50 SK CMT.

3RD Plug @ 240 FT W/40 SK CMT., 4th Plug HULL'S-PLUG @ 40 FT W/10 SK CMT.

NO RAT HOLE. CEMENTED BY ALLIED CMT.

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (Eli Hammersonmiot / did not) observe this plugging.

INVOICED

DATE 3-29-84

INV. NO. 0985-3-22

RECEIVED STATE CORPORATION COMMISSION 3-26-84 MAR 26 1984 CONSERVATION DIVISION Wichita, Kansas

Signed Eli Hammersonmiot (TECHNICIAN) 201C