

4-080231

TO:

API number: 15- 179-21,098-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

~~KC/S~~ NW NE NW /4 SEC: 12 - 09 - 28 W
535 Feet from N (N/S) Line
1645 Feet from W (E/W) Line

Operator License 4748

12/29

LEASE: Haffner WELL # 1

Operator: A & A DISCOVERY, INC.,

County: SHERIDAN 134.55

Address: 748 S. 4th St.
Hill City, Kansas
67642

Well total Dept 4140 feet
Conductor Pipe _____ inch @ _____ feet
Surface pipe 8 5/8 inch @ 218 feet

Aband. Oil Wel _____ Gas Well _____ Input Wel _____ SWD: _____ D & A: X

Plugging contractor: Vonfeldt Drilling Co. License#: 9431

Address: Russell, Ks

Company to plug at: _____ Hour: ?? Day: _____ Month: _____ Year: _____

Plugging proposal received fro Bill Owens

Company: Vonfeldt Drilling Co. Phone: _____

Were: Spot plugs through drill pipe w/ heavy mud between all plugs

1 st plug 2380 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 1460 feet with 100 sacks Mouse hole 10 sacks
3rd plug 270 feet with 40 sacks Wiper plug @ 40 foot
4th plug 40 feet with 10 sacks
5th plug _____ feet with _____ sacks

Plugging proposal recived by Bruce Basye

Pluggings operations attended by agent? All [], Part [], None [X]

Completed Hour: 05:00 AM Day: 29 , Month: December Year: 1999

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 Posmix w/ 6% gel and _____ sx celloflake or flowcel.

Remarks: Elevation: 2735 GL, Anhydrite top: 2361 feet Anhy. plug: Y

Dakota plug: Y Bottom plug in plac N

Plugged through drill pip C

Arbuckle top _____ Cemented by: Allied Cementing

I did [] did NOT [X] observe the plugging

Bruce Basye
Bruce Basye (agent)

INVOICED
DATE 1/10/00
INV. NO. 061081

RECEIVED
STATE CORPORATION COMMISSION
1-4-00
JAN 04 2000

CONSERVATION DIVISION
Wichita, Kansas

Form CP-2/3

(Handwritten mark)