

4-061216

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-21,098-0001

NW NE NW /4 SEC. 12, 09 S, 28 W
4745 feet from S section line
3635 feet from E section line

Operator license# 4748

Lease: Haffner Well # 1 OWWO

Operator: A&A Discovery, Inc.

County: Sheridan 148.98

Address: 748 S. 4th Street
Hill City, Kansas 67642

Well total depth 4584 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 200 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: VonFeldt Drilling Company License# 9431

Address: Russell, Kansas 67665

Company to plug at: Hour: 12:30 A.M. Day: 10 Month: January Year: 2000

Plugging proposal received from: Bill Owen

Company: VonFeldt Drilling Company Phone: -

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Re-entered well to test zone and deepen well. P&A.


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 3:15 A.M., Day: 10, Month: January, Year: 2000

Actual plugging report:
1st. Plug at 2380' w/25 sxs cement.
2nd. Plug at 1460' w/100 sxs cement.
3rd. Plug at 270' w/40 sxs cement.
4th. Plug at 40' w/10 sxs cement.

Remarks: Allied Cementing.
Condition of casing in hole): GOOD___ BAD___ Anhy.plug: YES X NO___
Bottom plug(in place): YES___, CALC___, NO___ Dakota plug: YES X, NO___
Plugged through TUBING___, CASING___ Elevation: 2735 GL

I did[] / did not[X] observe the plugging.


(agent)

INVOICED
DATE 1/20/00
INV. NO. 061151

RECEIVED
STATE CORPORATION COMMISSION
1-20-00
JAN 20 2000

CONSERVATION DIVISION
Wichita, Kansas

