

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20675-00-08²
Spot: S2SWSWNE Sec/Twnshp/Rge: 14-10S-16W^{AT KCC}
2860 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ROGERS Well Number: 1-A
County: ROOKS Total Vertical Depth: 3616 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 273 w/175 sxs cmt
Production: Size 5.5 feet: 3614 w/75 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/23/2001 1:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/23/2001 2:45 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 273'.w/175 sxs cwc.
5 1/2" set at 3614' w/75 sxs.
Cement squeezes in 5 1/2" with cement in cellar to top of 5 1/2" collar.
Prod Perfs 3583' - 3586'; 3590' - 3594'.
Squeezed 5 1/2" w/250 sxs cement blend w/500# hulls mixed in to Max. P.S.I. 800# Held.
Plug complete.

Remarks: LEASE READS AS FOLLOWS: 110'S.OF SWSWNE 14-10-16W. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

RECEIVED

INVOICED

OCT 30 2001

DATE 10-30-01

KCC WICHITA

INV. NO. 2002060880

Form CP-2/3

OCT 25 2001

MURFIN DRLG. CO. #1-A ROGERS 14-10-16W
 617 UNION CENTER WICHITA, KS. 110'S, SW SW NE
 CONTR. PICKRELL DRLG. CO. CITY - ROOKS

GEOL. FIELD NATOMA EXT (1/8 NE)

2073 KB CM 1/14/77 CARD ISSUED 6/16/77 IP TEMP ABD

+	+	+
+	+	+
+	+	+

API 15-163-20,675

SMP	TOPS	DEPTH	DATUM
ANH	1237	+ 836	
9 ANH	1273	+ 800	
TOP	2952	- 879	
HEEB	3182	-1109	
TOB	3204	-1131	
LANS	3228	-1155	
BKC	3480	-1407	
COND SD	3580	-1507	
RTD	3616	-1543	

6-5/8" 273/175sx, 5 1/2" 3614/75sx
 NO LOG
 DST (1) 3555-84/30-30-30-30, 56' so SP7M,
 SIP 714-714#, FP 41-61#, 61-61#,
 BHT 105°
 DST (2) 3568-91/MIS-RUN
 DST (3) 3561-91/30-45-45-60, 70' so SP
 M, SIP 674-754#, FP 61-61#, 61-61#
 DST (4) 3591-3606/30-45-45-60, 40' M,
 SIP 714-674#, FP 41-51#, 51-51#,
 BHT 108°
 MICT ~ PF 3583 1/2-86, AC 250, SWB 25
 BFPH/2HRS, FRAC 4000GAL GEL AC + 15SX
 SO, REC LD & SWB 6.76BFPH, W/SC OF HO,
 PF 3590-94, SWB 98F, W/SC OIL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

022104