

6070527

NOV 21 1986

API NUMBER 15-163-22,899-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C-NE-SW, SEC. 14, T. 10 S, R. 16 W

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146 Lease Name Rogers - FLR Well # 1

Operator: Rains + Williamson Corp. County Rooks. 117.33

Name & Address 435 Page Court, 220 W. Douglas, Wichita, Kans. 67202 Well Total Depth 3610 feet

Maenita Green. Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 330

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rains + Williamson OREGON License Number 5146

Address 435 Page Court, 220 W. Douglas, Wichita, Kans. 67202

Company to plug at: Hour: 2:00 AM Day: 21st Month: Nov Year: 86

Plugging proposal received from Mike Godfrey DEC 8 1986

(company name) Rains + Williamson OREGON CONSERVATION DIVISION phone 271-265-9686

were: 8 5/8" SP. CEMENT / 200' 1/40 Pozmix 3% Ca. cl. 124 W.S. Titan

Proposal, Order 215 1/40 Pozmix 3% Ca. cl. - 1 1/2 slake and 8 5/8" Plug

Spotted with Drill stem, Recondition Hole, heavy Mud Between All Plugs. Displace

two Top Plugs with Mud. ELV. 2050 thk. 1228, No Circulation Problems, Mud

Condition 45. Vis, 9.7 Weight, 9.6 water, 25' @ 3570', 25' @ 1240', 100' 1/2 slake @ 750',

40' @ 360' Bridge @ 40' 1/10' Plugging Proposal Received by Maurine Schmidt (TECHNICIAN)

15' Rat Hole (circulate)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 2:00 AM Day: 21st Month: Nov Year: 86

ACTUAL PLUGGING REPORT Ordered 215 1/40 Pozmix 6% Ca. cl., 1 1/2 slake + 8 5/8" Plug

Spotted with Drill stem, Reconditioned Hole, heavy Mud Between all Plugs

Displaced First Two Plug with Mud.

1st Plug @ 3570' 1/25' cement, 2nd Plug @ 1240' 1/25' cement

3rd Plug @ 750' 1/100' cement 1/4 slake, 4th Plug @ 360' 1/40' cement

5th Plug 1/10' cement, 15' RAT HOLE (CIRCULATE)

Remarks: 11-24-86 (If additional description is necessary, use BACK of this form.)

IN WITNESS WHEREOF, I, GILBERT BALTHAZOR, signed Maurine Schmidt (TECHNICIAN)