

**KANSAS CORPORATION COMMISSION**  
**OIL & GAS CONSERVATION DIVISION**  
**WELL PLUGGING APPLICATION**  
*Please TYPE Form and File ONE Copy*

Form CP-1  
 March 2009  
**This Form must be Typed**  
**Form must be Signed**  
**All blanks must be Filled**

OPERATOR: License #: 30535  
 Name: Hartman Oil Co., Inc.  
 Address 1: 3545 W Jones  
 Address 2: \_\_\_\_\_  
 City: Garden City State: Ks Zip: 67846 + \_\_\_\_\_  
 Contact Person: Stan Mitchell  
 Phone: (620) 277-2511

API No. 15 - 083-21,447-01-00  
 If pre 1967, supply original completion date: 9/4/97  
 Spot Description: \_\_\_\_\_  
SW-SW SE SW Sec. 25 Twp. 22 S. R. 23  East  West  
205 Feet from  North /  South Line of Section  
1,458 Feet from  East /  West Line of Section  
 Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
 County: Hogdemam  
 Lease Name: Billings Well #: HZ-1

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
 Conductor Casing Size: N/A Set at: N/A Cemented with: N/A Sacks  
 Surface Casing Size: 9/5/8" Set at: 560' Cemented with: 225 Sacks  
 Production Casing Size: 7" Set at: 4812' Cemented with: 500 Sacks

List (ALL) Perforations and Bridge Plug Sets:  
 NOTE: (Horizontal Well) open hole 4812' - 6856'  
 4-1/2" slotted liner 4536' - 6856'  
 Elevation: 2281' ( G.L. /  K.B.) T.D.: 6856' PBDT: N/A Anhydrite Depth: 1428'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)  
 Proposed Method of Plugging (attach a separate page if additional space is needed):  
 as per kcc - NOTE: (Horizontal Well w/ Deviation starting @ 3965') SEE ATTACHED - RIH w/ CIBP - set @ 3965' or as low as possible - w/ 7 sks cement on CIBP - Run CBL from 1500' to surface - (if no cement) Perforate 2 holes @ 1450' & 2 holes @ 600' - RIH w/ TBG spot 75 sks 60-40 poz w/ 4% gel down TBG @ 1450 - POOH w/ TBG (w/o cement 3/Hrs.) - Circulate cement from 600' to surface w/ 200 sks 60-40 poz w/ 4% gel - (if no circulation) - pump 50 sks 60-40- poz w/ 4% gel down Csg/ Annulus - Cut CSG off @ 4' below ground level - weld & date cap on CSG w/ plugging date  
 Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No  
 If ACO-1 not filed, explain why:

KANSAS CORPORATION COMMISSION  
**MAY 15 2009**  
**RECEIVED**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.  
 Company Representative authorized to supervise plugging operations: Stan Mitchell - Hartman Oil Co., Inc.  
 Address: 3545 W Jones City: Garden City State: Ks Zip: 67846 + \_\_\_\_\_  
 Phone: (620) 277-2511  
 Plugging Contractor License #: 4072 33645 *Kcc Per* Name: H2 Plains LLC  
 Address 1: PO Box 346 *Per LLC* Address 2: \_\_\_\_\_  
 City: Ness City State: Ks Zip: 67560 + \_\_\_\_\_  
 Phone: (785) 798-3995

Proposed Date of Plugging (if known): as weather permits  
 Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent  
 Date: 5/5/09 Authorized Operator / Agent: A.T. Mitchell  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Dist 1*  
*PKT*



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

HARTMAN OIL CO., INC.  
10500 E BERKELEY SQ PKWY STE 100  
WICHITA, KS 67206

May 21, 2009

Re: BILLINGS #HZ-1  
API 15-083-21447-01-00  
25-22S-23W, 205 FSL 1458 FWL  
HODGEMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after November 17, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888