

15-109-20584-00-00

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-109-20,584-~~00-00~~ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Abercrombie Drilling, Inc. KCC LICENSE # 5422

ADDRESS 150 N. Main, Suite 801 (owner/company name) CITY Wichita (operator's)

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1841

LEASE Kolste WELL# 1 SEC. 7 T. 11S R. 32 (SW/West)

70'W - NE - NE - NE SPOT LOCATION/Q000 COUNTY Logan

330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

400 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 259.75' CEMENTED WITH 180 SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 3090/3095 T.D. 4653' PBD \_\_\_\_\_ ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill with heavy mud, 1st plug @ 2610' with 25 sks., 2nd plug @ 1700' with 100 sks., 3rd plug @ 310' with 40 sks., 4th plug @ 40' with 10 sks., 15 sks rathole, total 190 sks 60/40 posmix, 6% gel, with 1/4# floseal/sk. (If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# ( ) 316-262-1841

ADDRESS 150 N. Main, Ste 801 City/State Wichita, Ks. 67202

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684

(company name) (contractor's)  
ADDRESS 150 N Main, Ste 801, Wichita, Ks. PHONE # ( ) 316-262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 4:30 p.m. 03-22-95

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 03-23-95 AUTHORIZED OPERATOR/AGENT: Jack K. LePorter  
(signature) Vice President