

15-109-20536-00-00

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-109-20,536-00-00 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Slawson Exploration Company, Inc OPERATOR'S LICENSE NO. 3988

ADDRESS Lincoln, Suite 490, Oklahoma City, OK 73102-6217 PHONE # (800) 333-5493

LEASE (FARM) Nollette AB WELL NO. #1 WELL LOCATION SW SE SE COUNTY Logan

SEC. 7 TWP. 11S RGE. 33 (E) or (W) TOTAL DEPTH 4805' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A x SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 406' CEMENTED WITH 60-40 posmix-250 sx SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD x POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2700' w/25 sx; 2nd plug @ 2400' w/80 sx; 3rd plug @ 1800' w/40 sx; 4th plug @ 500' w/20 sx; 5th plug @ 40' w/10 sx; mousehole 10 sx; rathole 15 sx; 60-40 posmix 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? No
(If not explain.) Sent to Operator to complete.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9:00 a.m. 7-10-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Craig, Sr.

PHONE # (913) 674-2876

ADDRESS P.O. Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc.

LICENSE NO. 30684

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED
STATE CORPORATION COMMISSION
7-22-1992
JUL 22 1992

SIGNED:

Jack T. Wharton
(Operator or Agent)

DATE:

July 13, 1992