

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

AMENDED

Operator: License # 33365
Name: Layne Energy Operating, LLC
Address: 1900 Shawnee Mission Parkway
City/State/Zip: Mission Woods, KS 66205
Purchaser: _____
Operator Contact Person: M. B. Natrass
Phone: (913) 748-3987
Contractor: Name: MOKAT Drilling
License: 5831

Wellsite Geologist: _____
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____

Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>11/30/2005</u>	<u>12/1/2005</u>	<u>1/30/2006</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 125-30895 - 00 - 00
County: Montgomery
NW - NE - NW - Sec. 19 Twp. 31 S. R. 17 East West
500 feet from S / (circle one) Line of Section
1500 feet from E / (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: O'Brien Well #: 3-19
Field Name: Coffeyville - Cherryvale
Producing Formation: Cherokee Coals
Elevation: Ground: 910 Kelly Bushing: _____
Total Depth: 1204' Plug Back Total Depth: 1194'
Amount of Surface Pipe Set and Cemented at 20' Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 1201'
feet depth to Surface 06 - 7/10/08 w/ 120 sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content N/A ppm Fluid volume _____ bbls
Dewatering method used N/A - Air Drilled
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.


Signature: MB Natrass

Title: Agent Date: 3/27/06

Subscribed and sworn to before me this 27th day of March

Notary Public: Brooke C. Maxfield

Date Commission Expires: _____



KCC Office Use ONLY

Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 10 2008

Operator Name: Layne Energy Operating, LLC Lease Name: O'Brien Well #: 3-19
 Sec. 19 Twp. 31 S. R. 17 East West County: Montgomery

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <i>(Attach Additional Sheets)</i>	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Pawnee Lime	582 GL	328
Electric Log Run <i>(Submit Copy)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Excello Shale	708 GL	202
List All E. Logs Run:		V Shale	761 GL	149
Compensated Density Neutron		Mineral Coal	804 GL	106
Dual Induction		Mississippian	1104 GL	-194

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacjs Used	Type and Percent Additives
Surface	11"	8.625"	24	20'	Class A	4	Type 1 cement
Casing	6.75"	4.5"	10.5	1201'	Thick Set	120	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
	See Attached		

RECEIVED
 KANSAS CORPORATION COMMISSION
JUN 10 2008
 CONSERVATION DIVISION
 WICHITA, KS

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2-3/8"	1075'		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.	Producing Method			
6/22/2006	<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio Gravity
	0	54	0	

Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

Operator Name:	Layne Energy Operating, LLC.		
Lease Name:	O'Brien 3-19		
	Sec. 19 Twp. 31S Rng. 17E, Montgomery County		
API:	15-125-30895-00-00		
Shots per Foot	Perforation Record	Acid, Fracture, Shot, Cement Squeeze Record	Depth
4	1031-1032.5, 917-918, 819.5-820.5, 803.5-805	Rowe, Bluejacket, Scammon A, Mineral-3400# 20/40 sand, 1200 gal 15% HCl, 362 bbls wtr	803.5-1032.5
4	761-763, 738.5-740, 707-712.5, 682-685.5, 627-628.5, 621.5-622.5	Croweberg, Ironpost, Mulky, Summit, Lexington B, Lexington A - 7800# 20/40 sand, 3000 gal 15% HCl, 615 bbls wtr	621.5-763

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 10 2008

CONSERVATION DIVISION
WICHITA, KS