

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 33344
Name: Quest Cherokee, LLC
Address: 211 W. 14th Street
City/State/Zip: Chanute, KS 66720
Purchaser: Bluestem Pipeline, LLC
Operator Contact Person: Jennifer R. Ammann
Phone: (620) 431-9500
Contractor: Name: TXD
License: 33837

Wellsite Geologist: Ken Recoy
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

1/26/07	1/28/07	2/28/07
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 133-26769-00-00
County: Neosho
_____-_____-_____
Sec. 15 Twp. 27 S. R. 18 East West
750 feet from S (circle one) Line of Section
660 feet from (circle one) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Beach, Don E. Well #: 15-1
Field Name: Cherokee Basin CBM
Producing Formation: multiple
Elevation: Ground: 908 Kelly Bushing: n/a
Total Depth: 967 Plug Back Total Depth: 963.3
Amount of Surface Pipe Set and Cemented at 44 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 963.3
feet depth to surface w/ 115 sx cmt.

Drilling Fluid Management Plan Alt II NW 7-9-08
(Data must be collected from the Reserve Pit)
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Jennifer R. Ammann
Title: New Well Development Coordinator Date: 5/23/07
Subscribed and sworn to before me this 23rd day of May, 2007.
Notary Public: Corra Klaueman
Date Commission Expires: 8-4-2010

KCC Office Use ONLY

Letter of Confidentiality Received
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 24 2007
CONSERVATION DIVISION
WICHITA, KS

TERRA KLAUMAN
Notary Public - State of Kansas
My Appt. Expires 8-4-2010

Operator Name: Quest Cherokee, LLC Lease Name: Beach, Don E. Well #: 15-1
 Sec. 15 Twp. 27 S. R. 18 East West County: Neosho

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Dual Induction Log Compensated Density Neutron Log Gamma Ray Neutron Log	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum See attached
---	--

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4	8-5/8"	20	44	"A"	25	
Production	6-3/4	4-1/2	10.5	963.3	"A"	115	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	931-934	300gal 15%HCLw/ 26 bbls 2%Kcl water, 333bbls water w/ 2% KCL, Biocide, 1700# 20/40 sand	931-934
4	638-640/605-608	300gal 15%HCLw/ 46 bbls 2%Kcl water, 386bbls water w/ 2% KCL, Biocide, 5100# 20/40 sand	638-640/605-608
4	513-517/503-507	300gal 15%HCLw/ 41 bbls 2%Kcl water, 563bbls water w/ 2% KCL, Biocide, 9200# 20/40 sand	513-517/503-507

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2-3/8"	946	n/a	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Date of First, Resumerd Production, SWD or Enhr. 3/22/07	Producing Method
	<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	n/a	0mcf	25.6bbls		

Disposition of Gas	METHOD OF COMPLETION	Production Interval
<input type="checkbox"/> Vented <input checked="" type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	<input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	_____

QUEST

Resource Corporation

211 W. 14TH STREET,
CHANUTE, KS 66720
620-431-9500

TICKET NUMBER **2052**

FIELD TICKET REF # _____

FOREMAN Joe

611970

TREATMENT REPORT & FIELD TICKET CEMENT

DATE	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY	
2-28-07	Beach Dan 15-1		15	27	18	No	
FOREMAN / OPERATOR	TIME IN	TIME OUT	LESS LUNCH	TRUCK #	TRAILER #	TRUCK HOURS	EMPLOYEE SIGNATURE
Joe B	6:45	10:30		903427		3.75	<i>Joe B</i>
Maverick D	7:00			903197		3.5	<i>Maverick D</i>
Russell A	7:00			903103		3.5	<i>Maverick D</i>
Paul H	6:45			902142	932452	3.75	<i>Paul H</i>
Gary C	6:45	✓		931500		3.75	<i>Gary C</i>

JOB TYPE Logging HOLE SIZE 6 3/4 HOLE DEPTH 965.70 CASING SIZE & WEIGHT 4 1/2 10.5
 CASING DEPTH 963.30 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.5 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 0
 DISPLACEMENT 15.36 DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS:

Installed cement head Ran 2 sks gel & 9 bbl dye & 115 sks of cement
 To get dye to surface. flush pump. Pump wiper plug to bottom & set float shoe

	963.30	ft 4 1/2 Casing
	5	Centralizers
903140	2 hr	Casing tractor
	2 hr	Casing trailer

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION OF SERVICES OR PRODUCT	TOTAL AMOUNT
903427	3.75 hr	Foreman Pickup	
903197	3.5 hr	Cement Pump Truck	
903103	3.5 hr	Bulk Truck	
1104	110 SK	Portland Cement	
1124	2	50/50 POZ Blend Cement Baffle 3 1/2 43	
1126	1	OWC Blend Cement 4 1/2 wiper plug	
1110	11 SK	Gilsonite	
1107	1 SK	Flo-Seal	
1118	2 SK	Premium Gel	
1215A	1 gal	KCL	
1111B	2 SK	Sodium Silicate Calchloride	
1123	7000 gal	City Water	
902142	3.75 hr	Transport Truck	
932452	3.75 hr	Transport Trailer	
931500	3.75 hr	80 Vac	

RECEIVED
KANSAS CORPORATION COMMISSION


MAY 24 2007

CONSERVATION DIVISION
WICHITA, KS

1 1/2 float shoe

QUEST

Resource Corporation



211 W. 14TH STREET,
CHANUTE, KS 66720
620-431-9500

SSL 911970

TICKET NUMBER 1901

FIELD TICKET REF # _____

FOREMAN Dwayne

TREATMENT REPORT & FIELD TICKET CEMENT

DATE	WELL NAME & NUMBER				SECTION	TOWNSHIP	RANGE	COUNTY
1-26-07	Beach# Dan 15-1				15	27S	18E	NO
FOREMAN / OPERATOR	TIME IN	TIME OUT	LESS LUNCH	TRUCK #	TRAILER #	TRUCK HOURS	EMPLOYEE SIGNATURE	
Dwayne	11:30	4:00		901640		hr	<i>[Signature]</i>	
Tim	11:30	3:30		903197		hr	<i>[Signature]</i>	
Russell	11:30	3:30		903206		hr	<i>[Signature]</i>	

JOB TYPE Surface HOLE SIZE 11" HOLE DEPTH 45' CASING SIZE & WEIGHT 8 5/8"
 CASING DEPTH 45' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.5 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 2.5 DISPLACEMENT PSI _____ MIX PSI _____ RATE 3 BPM

REMARKS:

Hook onto Surface casing and wash to TD then pump Pump 25 SK cement and Displace casing with 2.5 BPM water and Shut In.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION OF SERVICES OR PRODUCT	TOTAL AMOUNT
901640	4.5 hr	Foreman Pickup	
903197	4 hr	Cement Pump Truck	
903206	4 hr	Bulk Truck	
1104	25 SK	Portland Cement	
1124		50/50 POZ Blend Cement	
1126		OWC - Blend Cement	
1110		Gilsonite	
1107		Flo-Seal	
1118		Premium Gel	
1215A		KCL	
1111B		Sodium Silicate	
1123	1000 gal	City Water	
		Transport Truck	
		Transport Trailer	
		80 Vac	

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 24 2007
CONSERVATION DIVISION
WICHITA, KS