

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-109-20,510-00-00

LEASE NAME Wiens

15-109-20510-00-00

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2640 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 8 TWP. 11 RGE. 33 (E) or (W)

LEASE OPERATOR Viking Resources, Inc.

COUNTY Logan

ADDRESS 105 S. Broadway, #1040, Wichita, KS 67202

Date Well Completed 5/20/91

PHONE# (316) 263-2502 OPERATORS LICENSE NO. 5011

Plugging Commenced 5/20/91

Character of Well D&A

Plugging Completed 5/20/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/20/91 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4710 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Surface		272'	0'	8-5/8"	272'	None

7-15-1991  
1111 15 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged with 200 sacks 60/40 Pozmix, 6% gel, 1/4# flo seal/sk as follows:

25 sx @ 2670', 100 sx @ 1660', 40 sx @ 280', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 6:30 p.m. 5/20/91.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Viking Resources, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Shawn P. Devlin (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn P. Devlin

(Address) 105 S. Broadway Ste 1040 Wichita KS 67202

SUBSCRIBED AND SWORN TO before me this 20th day of June, 1991



Paula R. Dunagan  
Notary Public