

15-109-20507-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,507-00-00

LEASE NAME HECKER

WELL NUMBER #1-9

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 9 TWP. 11S RGE. 33 ~~000~~ or (W)

COUNTY LOGAN

Date Well Completed 4-16-91

Plugging Commenced 4-16-91

Plugging Completed 4-16-91

LEASE OPERATOR LANDMARK OIL EXPLORATION, INC.

ADDRESS 250 N. WATER, SUITE 308 Wichita, KS. 67202

PHONE# (316) 265-8181 OPERATORS LICENSE NO. 06113

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 15, 1991 (date)

by Herb Menzer (KCC District Agent's Name).

Is ACO-1 filled? by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4759'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	334'	8 5/8"	334'	none

4-24-1991
APR 24 1991

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

25 sx. @ 2640', 100 sx. @ 1630', 40 sx. @ 385', 10 sx. @ 40', 15 sx. in rathole

TOTAL: 190 sx. 60/40 Pozmix, 6% Gel 1/4# floseal per sack

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. (Halliburton) License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Landmark Oil Exploration, Inc.


STATE OF KANSAS COUNTY OF BARTON, ss.

Greg Davidson (Employee of Operator) or (~~OFFICER~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, KS. 67530



SUBSCRIBED AND SWORN TO before me this 22nd day of April, 19 91

Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-93

15-109-20507-00-00
DRILLER'S WELL LOG

COMMENCED: 4-06-91
COMPLETED: 4-16-91

LANDMARK OIL EXPLORATION, INC.
Hecker #1-9
NW NW NE Sec. 9-T11S-R33W
Logan County, KS.

0 - 334 Surface
334 - 2621 Shale
2621 - 2648 Anhydrite
2648 - 3285 Shale & Lime
3285 - 4759 Lime & Shale
4759 RTD

ELEVATION: 3130'GR 3135'KB

FORMATION DATA:

Anhydrite	2621'	(-514')
B.Anhydrite	2648'	(-487')
Heebner	4047'	(-912')
Toronto	4072'	(-937')
Lansing "A"	4086'	(-951')
Muncie Creek	4228'	(-1093')
BKC	4357'	(-1222')
Pawnee	4507'	(-1372')
Myric Station	4544'	(-1409')
Ft. Scott	4562'	(-1427')
Cherokee	4590'	(-1455')
Johnson	4631'	(-1496')
Mississippi	4704'	(-1569')
RTD	4759'	(-1624')

SURFACE CASING:

8 5/8" Set @ 334' W/220 sx. 60/40 pozmix,
2% Gel, 3% CC


A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{SS}

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.


Greg Davidson

Subscribed and sworn to before me this 22nd day of April, 1991.




Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-93

RECEIVED
STATE CORPORATION COMMISSION
4-24-1991
APR 24 1991
CONSERVATION DIVISION
Wichita, Kansas