

15-063-20152-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-31-1973
JAN 31 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company,
Complete Address 617 Union Center, Wichita, Kansas.
Lease Name Little Well No. 1
Location CNW-SE Sec. 34 Twp. 11 Rge. (E) (W) 30
County Gove Total Depth 4600'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 2:00 AM Day 29 Month 1 Year 1973

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1425' and displaced 110 Cu. F t.cement
thru DP from 1425' to 1100'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols
Well Plugging Supervisor

INVOICED

1/31/73

6929-W

NOV 30 1973