

15-109-00013-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 121-13
LOCATION NW SE 3rd
SEC. 3 TWP. 7 RGE. 30

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Deftend

Operator Lawrence Supply Co Address c/o West Supply Chase, Kans

Field County Logan

Total Depth 4750 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address

(Describe briefly the manner in which the well was plugged)

8 5/8" at 277' circulated with cement - 5 1/2" at 4738' with 150
sax cement behind.

Filled with sand to 4730', set 4 sax cement with dump bailer,
pulled 1900' 5 1/2" - filled with mud to 270', set rock and 20 sax
cement, heavy mud to 35', set rock and 10 sax cement to bottom
cellar.

Edna Peery
District Conservation Agent
Date 12-22-56

PLUGGING
FILE NO. 3 T. 11 R. 30
SEC. 3 TWP. 7 RGE. 30
LINE 13

12-26-1956