

15-109-20018-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-29-1973
JAN 29 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Swart Well No. D-1

Location App:-CE/2-SW-NW Sec. 12 Twp. 11 Rge. (E) (W) 32

County Logan Total Depth 4700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 11:25 AM Day 26 Month 1 Year 1973

The above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 110 Cu. Ft. cement
thru DP from 1675' to 1350'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/8 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Dinkel
Well Plugging Supervisor

INVOICED

DATE 1/30/73
INV. NO. 6903-W