

15-109-20011-00-00

Form CP-3
Rev. 6-4-68

KANSAS

4 STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
8-9-1971
AUG 9 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin - Nadel & Gussman - Raymond Oil

Complete Address 617 Union Center Wichita, Kansas

Lease Name Johnson "H" Well No. 1

Location A/C NW NW Sec. 14 Twp. 11 Rge. (E) (W) 32

County Logan Total Depth 4705'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11 P Day 2 Month 8 Year 1971

The above well was plugged as follows:

BTD 4705' 8 5/8 csg set at 288' cwc 175 sk. Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 1650' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ken J. Massey
Well Plugging Supervisor

DATE 8-10-71

INV. NO. 4122-W