

15-109-20017-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
12-12-1972  
DEC 12 1972

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,  
 Complete Address R. R. #2, Victoria, Kansas.  
 Lease Name Webber Well No. 1  
 Location CNW-NE Sec. 11 Twp. 11 Rge. (E) (W) 32  
 County Logan Total Depth 4687'  
 Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
 Other well as hereafter indicated         
 Plugging Contractor John O. Farmer, Incorporated,  
 Address Box #352, Russell, Kansas. License No.         
 Operation Completed: Hour 8:30 PM Day 7 Month 12 Year 1972

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 1500'.

Circulated hole with heavy mud. Pulled DP to 1725' and displaced 110 Cu. Ft. cement  
thru DP from 1725' to 1400'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge 140' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. G. Nichols*  
Well Plugging Supervisor

RECEIVED  
DATE 12/12/72  
INVEST. 6721-U