

15-109-00027-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SE

SEC. 15 TWP. 11 RGS2 32

Dry Hole x Abandoned Oil Well Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Sharp

Operator Skiles Oil Corp Address Wichita, Kans

Field County Logan

Total Depth 4761 Feet.

(Describe briefly the manner in which the well was plugged)

200 Sax

10" at 176' circulated with ~~125~~ sax cement - 5 1/2" at 4690'

with 125 sax cement behind, perforated at 4300' squeezed

with 200 sax cement, P.B. to 4313' - top perforation 4300'.

Filled with chat to 4300' set 4 sax cement with dump bailer .

Pulled 1503' 5 1/2", filled hole with mud to 185', set rock

to 175', set 20 sax cement at 175', filled with mud to 35',

set rock and 10 sax cement to bottom cellar.

PLUGGING

FILE SEC 15 T 11 R 320

BOOK PAGE 143 LINE 44

3-15-1952

District Conservation Agent

Date 3-8-52