

15-109-20008-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

*Y*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
11-23-1970  
NOV 23 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Alpine Drilling Company, Incorporated,  
Complete Address 800 Bitting Building, Wichita, Kansas.  
Lease Name Nollette Well No. 1  
Location CSE-SW Sec. 7 Twp. 11 Rge. (E) (W) 33  
County Logan Total Depth 4800'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Gabbert-Jones, Incorporated,  
Address 830 Sutton Place, Wichita, Kansas. License No.         
Operation Completed: Hour 9:45 AM Day 17 Month 11 Year 1970

The above well was plugged as follows:

28 1/2'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1375'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 100 Sx. cement thru  
DP from 1600' to 1275'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from  
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Pichels*  
Well Plugging Supervisor

RECEIVED  
11-25-70  
WV. NO. 2905-W