

15-109-20113-00-00

Form CP-3
Rev. 6-4-68

12

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -109 -20,113-00-00 (of this well)

RECORDED
STATE OF KANSAS
SEP 28 1978
9-25-1978
OFFICE OF THE COMMISSIONER
CONSERVATION DIVISION

Operator's Full Name Donald C. Slawson

Complete Address 200 Douglas Bldg., Wichita, Kansas

Lease Name Hecker "C" Well No. 1

Location C NE NW Sec. 9 Twp. 11 Rge. (E) (W) 33

County Logan Total Depth 4790'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 6:15 P Day 21 Month 9 Year 1978

The above well was plugged as follows:

RTD 4790' 8 5/8 csg set 542' cwc Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 1500' thru drill pipe.
Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

9-26-78
INV. NO. 8154.W