

15-109-00001-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

12-5-1962  
DEC 5 1962

Operator's Full Name Fender Pipe & Supply

Complete Address: Box 302 Russell, Kans

Lease Name Rohrs Well No. 1

Location CNE NW Sec. 18 Twp. 11 Rge. (E) (W) 33

County Logan Total Depth 4840

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Barnes & Sons Pipe Pulling

Address: Russell, Kansas License No. 9

Operation Completed: Hour 10AM Day 2 Month 12 Year 62

The Above well was plugged as follows:

8 5/8" 240' circulated with cement - 5 1/2" 4740' with 125 sax cement.  
perf 4525'

Plugs and sand back to 4160', set 5 sax cement with dump bailer at 4160',  
pulled 2360' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" at  
600' ( 28 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy mud to  
210', displaced 20 sax cement through 5 1/2" at 210', heavy mud to 35', cement  
35' to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Edna Perry  
Well Plugging Supervisor

INVOICED

DATE 12/10/62  
INV. NO. 6182-W