

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-1-64
JUN 1 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Green Pipe & Supply Co
Complete Address: Box 1383 Tulsa, Okla
Lease Name Kempe Well No. 3
Location NW SE SW Sec. 31 Twp. 10 Rge. (E) (W) 17
County Rooks Total Depth 3692
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Bert Self & Globe Cementing Co
Address: Hutchinson, Kans License No. 48
Operation Completed: Hour 11AM Day 27 Month 5 Year 64

The Above well was plugged as follows:

8 5/8" 1367' circulated with cement - 5 1/2" 3682' with 250 sax cement.

Sand back to 3670', set 4 sax cement with dump bailer - pulled 2250'
5 1/2" to 500', circulated hole with heavy gel mud through 5 1/2" - displaced
20 sax cement through 5 1/2" at 500', heavy mud to 200', displaced 20 sax
cement through 5 1/2" at 200', heavy mud to 35', cement 35' to 0'.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6/2/64
INV. NO. 9235-11