

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

6-5-64
JUN 5 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Green Pipe & Supply
Complete Address: Box 1383 Tula, Okla
Lease Name Kempe Well No. 4
Location NW NE SW Sec. 31 Twp. 10 Rge. (E) (W) 17
County Rooks Total Depth 3660
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Bert Self
Address: Hutchinson, Kans License No. 48
Operation Completed: Hour 10 am Day 2 Month 6 Year 64

The Above well, was plugged as follows:

8 5/8" 143' circulated with cement - 5 1/2" 3654' with 125 sax cement &
squeezed in Dakota with 200 sax cement - 2" packer set at 1350' -
unable to pull packer - shot 2" off at 1350' - set 4 sax cement
on packer at 1350' - circulated hole with heavy mud through 5 1/2" at 500' -
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 200'.
displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35' -
cement 35' to 0' - recovered 600' 5 1/2" -

Mudding and cementing by Glöbe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edwin Kelly*
Well Plugging Supervisor

INVOICED

DATE 6/5/64
INV. NO. 9267-11