

15-163-01854-0000

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4-24-78  
APR 24 1978  
CONSERVATION DIVISION  
Wichita, Kansas  
(of this well)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

Operator's Full Name Tenneco Oil Co.

Complete Address 3000 Founders Blvd., Suite 139, Ciudad Bldg., Oklahoma City, Okla.  
73112

Lease Name Kempe "A" Well No. 5

Location C SE NE SW Sec. 31 Twp. 10 Rge. (E) (W) 17

County Books Total Depth 3653'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12 N Day 21 Month 4 Year 1978

The above well was plugged as follows:

Total Depth 3653' 8 5/8 csg set 161' cwc 100 sk.

5 1/2 csg set 3637' cw 250 sk cem. Sq. at 609' W/175 sk cem. circ to surface.

4 1/2 csg liner set 3649 1/2 cw 200 sk cem.

Castiron plug at 3510' & perf. (3470'-3463')

Filled 4 1/2 csg W/sd to 3400' -dumped 3 sk cem W/dump bailer. No pipe rec

Cutoff & recovered 430' of 4 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 5 1/2 csg with 35 sk "Halliburton-Light"  
cement from 430' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

4-25-78  
7176-u

Signed: Lio Massey  
Well Plugging Supervisor