

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

1-21-63
JAN 2 - 1963

Operator's Full Name Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Lease Name Ridler Well No. 1

Location SE SW NW Sec. 31 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3634

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Ralph Lynch

Address: Great Bend, Kans License No. 457

Operation Completed: Hour 5PM Day 16 Month 1 Year 62 63

The Above well was plugged as follows:

8 5/8" 238' circulated with cement - 5 1/2" 3630' cement survey 3020'
PB to 3505' - perforated ? - plugged back with sand to 3200', set 4 sax
cement with dump bailer.

Pulled 1810' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2"
at 550' - displaced 20 sax cement through 5 1/2" at 550', heavy gel mud to
180', displaced 20 sax cement through 5 1/2" at 180', heavy gel mud to
35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Lynch Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
1/21/63
INV. NO. 6462-W

Signed: Eldon Petty
Well Plugging Supervisor