

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 9 TWP. 10 RGE. 17 E/W
Location as in quarters or footage from lines:
SW NE SW

Lease Owner Horizon Petroleum Corp.
 Lease Name Fritz Well No. #3
 Office Address 833 North Waco Wichita, KS 67203
 Character of Well (Completed as Oil, Gas or Dry Hole):
 Date Well Completed 8-26-82
 Application for plugging filed 8-26-82
 Plugging commenced 8-26-82
 Plugging completed 8-26-82
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
Producing formation _____ Depth to top _____ bottom _____ T.D. 3654'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug: @825' w/100 sacks 50/50 pozmix 6% gel thru drill pipe
Middle Plug: @260' w/40 " " " " " " " "
Top Plug: @40' w/solid bridge of 1/2 sack hulls & 10 sacks cement
10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney (~~owner or operator~~) (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
Box 823 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of August, 1982

Dorothy M. Hague

RECEIVED Public.
STATE CORPORATION COMMISSION

9-1-82
SFP 1 1982

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires: 4-29-86



DRILLER'S WELL LOG

DATE COMMENCED: August 20, 1982
 DATE COMPLETED: August 26, 1982

Horizon Petroleum Corp.
 FRITTE #3
 SW NE SW
 Sec. 9, T10S, R17W
 Rooks County, Ks.

ELEVATION: 2055 K.B.

0 - 1309' Surface Soil, Shale, Sand
 1309 - 1352' Anhydrite
 1352 - 2981' Shale & Lime
 2981 - 3244' Lime
 3244 - 3265' Shale
 3265 - 3286' Lime
 3286 - 3514' Lime
 3514 - 3630' Shale, Lime, Chert, Sand
 3630 - 3654' Dolomite
 3654' RTD

FORMATION DATA

Anhydrite	1309'
Topeka	2981'
Heabner	3244'
Toronto	3265'
Lansing K.C.	3286'
Base K.C.	4395'
Conglomerate	3514'
Arbuckle	3630'
RTD	3654'

Surface Pipe: Set new 8-5/8",
 20# pipe at 247' w/150 sacks
 60/40 pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and
 statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this _____ day of August 1982.

My Comm. Expires:

4-29-86

 Notary Public