

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 9 Twp. 10 Rge. 17 (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Isern Drilling Company

Lease Name B. Jones Well No. 1

Office Address Box 45, Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 20, 1954 19

Application for plugging filed May 20, 1954 19

Application for plugging approved May 20, 1954 19

Plugging commenced May 20, 1954 19

Plugging completed May 20, 1954 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elton Petty

Producing formation Depth to top Bottom Total Depth of Well 2528' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	184'	8-5/8"	184'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 180'.
Set bridge plug at 180', ran 15 sacks
cement 180' up. Filled hole with heavy
mud to 40'. Set bridge plug at 40', ran
10 sacks cement 40' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1954
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Isern Drilling Company
Address Box 45, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON
K. M. M. Shropshire (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Shropshire
Lyons, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 1954

George A. Meyer
Notary Public.

My commission expires Feb. 10, 1955.

PLUGGING
FILE SEC 9 T 10 R 17W
BOOK PAGE 36 LINE 5

WELL LOG

Isern Drilling Company etal, Owner - B. Jones #1
NE/4 NE/4 NE/4 Section 9, Township 10, Range 17W,
Rooks County, Kansas

ELEVATION: 2047 DF

Figures indicate bottom of formation
0 to 35 sand

PIPE RECORD:

8-5/8" set at 184'

100	shale
427	shale & shells
485	sand & shale
580	shale & shells
630	sand & shale
670	shale & shells
770	sand & shale
870	shale & shells
950	sand
970	shale & shells
1000	sand
1291	shale & shells
1325	Anhydrite
1595	shale & shells
1800	salt
1980	shale & shells
3105	lime & shale
3445	lime
3472	lime & shale
3528	Arbuckle lime
3528	Total Rotary Depth D & A

Rotary Commenced 5-11-54
Completed 5-20-54

STATE OF KANSAS)
COUNTY OF BARTON) ss

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

PLUGGING
 FILE SEC 7 T 10 R 17W
 BOOK PAGE 36 LINE 5

M. M. Shropshire

Subscribed and Sworn to before me this 21st day of May, 1954.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 22 1954
 CONSERVATION DIVISION
 Topeka, Kansas

George A. Meyer
Notary Public

My commission expires Feb. 10, 1955.