


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging of formations.

Rooks County Sec. 31 Twp. 10 Rge. (E) 17 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NE
Lease Owner Earl F. Wakefield
Lease Name Burnett "B" Well No. 2
Office Address 307 Union Natl. Bk. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 14 19 52
Application for plugging filed April 14 19 52
Application for plugging approved April 14 19 52
Plugging commenced April 14 19 52
Plugging completed April 14 19 52
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	108.45	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from 3670' to 180'. Placed Halliburton plug at 180' bridged with 1/2 sack hulls cemented with 15 sacks heavy mud to 40' bridged with Halliburton Plug and 1/2 sack of hulls cemented to bottom of cellar with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Earl F. Wakefield
Address 307 Union National Bank Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Earl F. Wakefield (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
307 Union Natl. Bk. Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of April, 1952

My commission expires 12-23-54

Notary Public
4-18-52
APR 18 1952

PLUGGING
FILE SEC 31 T 10 R 17 W
BOOK PAGE 8 LINE 34

2-48-15M
Wichita, Kansas

Burnett "B" #2
Owner: Earl F. Wakefield
Contractor: Earl F. Wakefield
Comm: 4-2-52 Comp: 4-14-52

NW NW NE 31-10-17W
Rooks County, Kansas
Casing: 8 5/8" 116'

Elevation 2042

Lime	72
Lime & Shale	90
Shale	310
Shale & Shells	560
Shale & Red Bed	710
Shale & Shells	1330
Anhydrite	1370
Shale & Shells	1430
Shale	1485
Shale & Shells	1850
Shale & Lime	2290
Lime & Shale	2875
Shale & Lime	3250
Lime & Shale	3274
Lime (Lansing-K.C.)	3486
Lime & Shale	3575
Lime	3604
Lime & Shale	3620
Lime (Arbuckle)	3670
Total Depth	3670

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the Burnett "B" #2 well located NW NW NE 31-10-17W, Rooks County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 16th day of April, 1952.

James Gaffney

My Commission Expires: 12-23-54



PLUGGING
SEC 31 T 10 R 7W
PAGE 8 LINE 34