


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

ROOKS Co. County. Sec. 31 Twp. 10S Rge. 17 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines 15W SE SW  
Lease Owner GREEN PIPE & SUPPLY CO  
Lease Name REMPLE Well No. 3  
Office Address 817 WRIGHT BLDG. TULSA, OKLA.  
Character of Well (completed as Oil, Gas or Dry Hole) OIL  
Date well completed 8-30 19 50  
Application for plugging filed \_\_\_\_\_ 19 \_\_\_\_\_  
Application for plugging approved MAY 11 19 64  
Plugging commenced MAY 25 19 64  
Plugging completed MAY 27 19 64  
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY  
Producing formation ARBUCKLE Depth to top 3620 Bottom 3688 Total Depth of Well 3689 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1365	0
				5 1/2	3688	2252

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled BACK IN THE 5" - DUMPED 4 SACKS OF CEMENT. SHOT PIPE OFF AT 2252.25'  
PULLED PIPE AND MUDDED HOLE TO 500'  
CIRCULATED WITH MUD - PUMPED IN 20 SACKS CEMENT. PULLED PIPE TO 200'  
PUMPED IN 20 SACKS OF CEMENT.  
DUMPED 10 SACKS OF CEMENT AT TOP.

RECEIVED  
STATE CORPORATION COMMISSION  
6-18-64  
JUN 18 1964

Name of Plugging Contractor BERT SEW (If additional description is necessary, use BACK of this sheet)  
Address HUTCHINSON, Kans.

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kans COUNTY OF REXO, ss.

EMPLOYEE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Sew  
R.R. #4 HUTCHINSON, KANS (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of MAY, 1964  
Oct. 18, 1965  
My commission expires \_\_\_\_\_

Notary Public.



15-163-01852-0000


WELL LOG BUREAU · KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - BAY PETROLEUM CORPORATION  
Farm - Kempe "A" No. 3

SEC. 31 T. 10 R. 17W  
NW SE SW

Total Depth. 3689 P.B. 3640  
Comm. 7-16-50 Comp. 8-30-50  
Shot or Treated.  
Contractor. John Lindas Oil, Inc.  
Issued. 9-16-50

County. Rooks  
KANSAS



Elevation. 2070 DF

Production. I.P. 364 BO / 2 1/2 wtr

Figures Indicate Bottom of Formations.

gyp rock	62
shale, shells	105
shale, shells, sand	170
shale, shells	400
shale, blue	675
sand iron	745
shale, sand, iron	775
shale, shells	838
sand	1045
shale, shells	1180
red bed, shells	1310
red bed	1350
anhydrite lime	1390
shale, shells	1470
red rock	1660
shale, shells	1920
shale, shells, lime	2270
lime	2335
lime, shale	2890
lime	3515
lime, chert	3570
lime, shale	3610
shale, lime	3644
lime	3689
Total Depth	
Plugged back	3640

Tops:

Anhydrite	1350
Heebner	3246
Dodge	3265
Lansing	3285
Arbuckle	3620

DST 3450-78 Open 40 min.  
Rec. 25' mud, few oil  
specks. BHP 720#.

DST 3477-3508 Open 35 min.  
Rec. 89' oil cut mud.  
BHP 1020#.

Ran Gamma Ray: 24 § 3650-58  
400' WPH.

Lane Well Plug top @ 3640  
24 § 3630-34 FU 1000' in  
55 min w/oil & 2600' /3  
hrs. / 5 G WPH

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1964

CONSERVATION DIVISION  
Wichita, Kansas