

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rooks SEC. 31 TWP. 10S RGE. 17W E/W  
Location as in quarters or footage from lines:  
SW NW SE

w			

Locate Well  
correctly on above  
Section Platt.

Lease Owner Tenneco Oil Company  
Lease Name Hahn #2 Well No. \_\_\_\_\_  
Office Address 3000 United Founders Blvd, Ciudad Bldg, Suite 139  
Character of Well (Completed as Oil, Gas or Dry Hole): Okla. City, Okla. 73112  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 4-27-82  
Plugging completed 4-30-82  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	151'	none
				5-1/2"	3629'	800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed bottom plug to 2640', ran 50' of sand and 5 sacks cement. Shot casing @2551', 1600', 1051' and 800'. Pulled a total of 26 joints of 5-1/2" casing. Plugged well with 4 sacks hulls, 10 sacks gel, 1 sack hulls, 70 sacks cement, 5 sacks gel, 8-5/8" plug and 70 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 176 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May 1982

My Commission expires:



Irene Hoover  
Notary Public.  
MAY 13 1982  
5-13-82  
CONSERVATION DIVISION  
Wichita Kansas

15-163-01847-0000  
4 extra copies please

HAHN #2


SW NW SE  
Sec. 31-10S-17W  
Rooks County, Kansas  
Ele. 2075 DF

Contractor: Lindsley Drilling Company  
Started 11/6/51 Finished 11/20/51

1-11-52

LOG

Clay - Rock	0 - 40	
Clay Shells	40 - 151	8-5/8" @ 151' w/100 Sx.
Shale-Clay-Shells	151 - 797	
Shale & Clay	797 - 1020	SLM @ 1000' - O.K.
Red Bed Sand	1020 - 1060	
Shale & Red Bed Breaks	1060 - 1290	
Anhydrite	1290 - 1380	
Shale & Chalk Lime	1380 - 1515	SLM @ 1500' - O.K.
Lime & Shale	1515 - 2190	SLM @ 2000' - O.K.
Lime & Shale	2190 - 2540	SLM @ 2500' - O.K.
Lime & Shale	2540 - 3265	Strapped D.P. in Derrick
Lime	3265 - 3369	
Lime & Shale	3369 - 3430	
Lime	3430 - 3468	
Lime & Shale	3468 - 3500	
Lime	3500 - 3522	
Lime & Shale	3522 - 3611	
Lime	3611 - 3630	T.D. 5 1/2" @ 3629' w/250 Sx.



TOPS

Heebner	3248
Toronto	3268
Lansing	3290
Conglomerate	3543
Arbuckle	3628
Total Depth	3630' D.F.

DST 3349-66 - gp 1 hr.  
Rec. 30' mud - 1700 FT  
DST 3444-79 -  
gp 1 hr., rec. 50' sh. o c m - 290 FT  
DST 3476-3519 - gp 1 hr.  
15' oil spbd. mud - 3' H o c m  
free oil in tool - 540 FT

STATE OF KANSAS )  
                          ) SS.  
COUNTY OF SEDGWICK )

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 16 1952  
CONSERVATION DIVISION  
Wichita, Kansas

I, Robt. K. Lindsley, do hereby certify that the above is a true and accurate log of the Hahn No. 1, located in the SW NW SE of Section 31-10S-17W, Rooks County, Kansas.

*Robt. K. Lindsley*  
Robt. K. Lindsley, Partner

Subscribed to and sworn before me this 26th day of November, 1951.

*Vera A. McKenzie*  
Notary Public

My Commission Expires September 18, 1952.