

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-109-20494-00-00

API NUMBER 15-109-20,494

LEASE NAME Seimers

WELL NUMBER 2

3960' Ft. from S Section Line

1320' Ft. from E Section Line

SEC. 34 TWP. 11S RGE. 33 (E) or (W)

COUNTY Logan

Date Well Completed _____

Plugging Commenced 11-16-90

Plugging Completed 11-16-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petex, Inc.

ADDRESS 1111 S. Glenstone Springfield, MO 65804

PHONE# (417) 862-2177 OPERATORS LICENSE NO. 8541

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-16-90 (date)

by Herb Dines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation Miss. Depth to Top _____ Bottom T.D. 4595'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	260.50'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fill w/heavy mud; set 1st plug @ 2590'-2390' w/50nsx; 2nd plug @ 1580'-1180' w/100 sx; 3rd plug @ 310'-150' w/40 sx; 4th plug @ 40'-surface w/10 sx; rathole 15 sx; 60-40 pozmix, 6% gel # Flocel per sack.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petex, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

1-3-1991

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 19 90



Angela Woodard
Notary Public

My Commission Expires: 3-20-93