

Kansas Corporation Comm.
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 109-20605 0000

15-109-20605-00-00

LEASE NAME Hubert "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 30 TWP. 11s RGE. 33 (X) or (W)

COUNTY Logan

Date Well Completed 12/12/95

Plugging Commenced 8:00AM 12/12/95

Plugging Completed 11:00AM 12/12/95

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 458 Hays, Kansas 67601

PHONE# (913) 625-6374 OPERATORS LICENSE NO. 3456

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/11/95 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.O. 4750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	STATE (If formation is in a different state, specify)	Size	Put In	Pulled out
			<u>8 5/8</u>	<u>399.25</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each plug.
1st Plug @ 2635' w/25sks 15sks In Rat Hole Circulated 1st Plug 15 Minutes w/ 51' Vis. Mud
2nd Plug @ 1660' w/100sks 10sks In Mouse Hole plugs displaced w/ drilling mud
3rd Plug @ 450' w/40sks
4th Plug @ 40' w/10sks Cement by Allied 200sks total 60/40 Poz 6% Gel w/ 1/4# FS/sk
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601-0763

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy, Inc.

STATE OF KANSAS COUNTY OF Ellis, ss.

Ed Glassman

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed: the same are true and correct, so help me God.

(Signature) Ed Glassman

(Address) P.O. Box 458

SUBSCRIBED AND SWORN TO before me this 11th day of Jan, 1996

Linda K Pfannenstiel
Notary Public

My Commission Expires: 2/15/96

